



MASON COUNTY ROAD COMMISSION

William Schwass, Chairman
Michael Ingison, Vice-Chairman
Jeff Conklin, Member

Mary Samuels, Manager/Director
Eric Nelson P.E., County Highway Engineer

JUNE 13, 2022

PROCESSED 22A or 22A-MODIFIED AGGREGATE (GRAVEL) & 2NS MATERIAL:

Sealed bids, faxed or emailed bids (enelson@masoncountyroads.com) will be received at the office of the Mason County Road Commission at 510 East State Street, Scottville, Michigan 49454 until 11:00 A. M., Tuesday June 28, 2022 for furnishing a minimum of 20,000 tons of aggregate (gravel) material and 10,000 cubic yards of associated ice control sand, or such lesser quantities as the bidder may be willing and able to supply prior to September 1, 2022. Material shall meet current MCRC Standard Specifications, see attached.

QUANTITY BEING BID

GRAVEL: _____ TON / CUBIC YARD (circle one)

ICE CONTROL SAND: _____ TON / CUBIC YARD (circle one)

Processed Aggregate (Gravel) Material

Delivered F.O.B. Scottville location: _____ per TON

Ice Control Sand Material

Delivered F.O.B. Scottville location: _____ per TON

Processed Aggregate (Gravel) Material

Suppliers Yard/Pit: _____ per CUBIC YARD

Ice Control Sand Material

Suppliers Yard/Pit: _____ per CUBIC YARD

Specify Location of Suppliers Yard/Pit: _____

Bids must be submitted in a sealed envelope bearing the name of the bidder and plainly marked as to the item in the best interest of the county of Mason.

FIRM BID SUBMITTED BY: _____ COMPANY NAME

_____ STREET ADDRESS

_____ CITY

_____ PHONE NUMBER

_____ EMAIL ADDRESS

Signed: _____

Closing Date 11:00 A.M. on Tuesday June 28, 2022

THE MASON COUNTY ROAD COMMISSION RESERVES THE RIGHT TO ACCEPT OR REJECT ANY AND ALL BIDS IN THE BEST INTERESTS OF THE ROAD COMMISSION AND TO WAIVE ANY MINOR IRREGULARITIES IN ANY BID.

MASON COUNTY ROAD COMMISSION
PROCESSED AGGREGATE (GRAVEL) SPECIFICATIONS

Description

This material shall be used for aggregate surfacing, patching and for aggregate base material under a hard surfacing. It is intended that this material shall be available for a period of at least one (1) year and possible multiple years.

The material may be delivered to the yard of the Mason County Road Commission, depending on the cost of hauling, or pickup by the MCRC at the Bidders yard.

22A-Modified Materials

This material shall be processed, well graded, and homogenous material. It shall consist of clean, hard, durable, course aggregate, free from clay lumps and soft or flaky material and shall conform to the following gradation. Any deviation of this gradation shall only be accepted if approved in writing by the Mason County Road Commission.

Sieve Size	% Passing
1"	100
¾"	90-100
3/8"	65-85
No. 8	30-55
Wash	6-10
Crushed	25% min

22A Materials

This material shall be processed, well graded, and homogenous material. It shall consist of clean, hard, durable, course aggregate, free from clay lumps and soft or flaky material and shall conform to the following gradation. Any deviation of this gradation shall only be accepted if approved in writing by the Mason County Road Commission.

Sieve Size	% Passing
1"	100
¾"	90-100
3/8"	65-85
No. 8	30-50
Wash	4-8
Crushed	25% min

2NS – Ice Control Sand

This material shall be processed, well graded, and homogenous material. The below gradation represents the target gradation for 2NS material. The 3/8, No.4 & No.8 sieve must follow the below requirements. The remaining sieves may vary depending on the quality of the materials excavated from the pit.

Sieve Size	% Passing
3/8"	100
No. 4	95-100
No. 8	65-95
No. 16	35-75
No. 30	20-55
No. 50	10-30
No. 100	0-10
Wash	0-3

Stockpile

Stockpile in the Bidders yard shall be secured in an area protected by a gate or fence or other means acceptable by the Mason County Road Commission. The Road Commission shall provide its own means for loading trucks. Stockpile must be available for one (1) to two (2) construction seasons depending on size and/or location of the pile.

Delivery of Materials

If MCRC elects to have material delivered to their yard:

- Delivery of materials may be over an extended period of time, not to exceed one (1) year.
- Scheduling of deliveries shall be as ordered by MCRC. Upon receipt of order, the successful Bidder(s) shall commence delivery within twenty-four (24) hours.

Testing

Aggregate (Gravel) gradation testing with passing results and Ice Control Sand gradation test results shall be provided by the Bidder(s) prior to final payment. MCRC reserves the right to do periodic independent assurance testing. Material determined to be not in compliance with the gradation may be rejected. Testing frequency shall be one (1) test for each 1,000 cubic yards or 1,500 tons.

Measurement and Payment

Measurement for material stockpiled in the supplier's yard shall be by **Cubic Yard**. The supplier shall certify to the amount present and guarantee amount. The MCRC reserves the right to do periodic stockpile cross sections to verify amounts.

Measurement of material delivered to the MCRC property in Scottville shall be by the **Ton** with the supplier to provide weight tickets from a certified scale for each load.

Payment shall be based on the unit price quoted by the ton or cubic yard whichever is bid and shall include all labor, equipment, and miscellaneous other costs to provide the material. No other additions shall be considered in the unit price.

Payment for material either stockpiled or delivered shall be over a minimum period of twelve (12) months - as agreed to by the Mason County Road Commission and the Contractor - beginning the first month after award, then continuing until the amount is paid off.

GRAVEL PROCESSING
BIDDERS LIST
2022

			<u>E-mail</u>	<u>Mail</u>	<u>Fax</u>
Hallack Contracting	4223 W. Polk Road Hart MI. 49420 Email: dhallack@hallackcontracting.com	Ph: 231-873-5081 fax: 231-873-2889	_____	_____	_____
Halliday Sand and Gravel	1128 Federal Ave Houghton Lake, MI 48629 Email: hallidaysandandgravel@gmail.com	Ph: 989-422-3463 fax: 989-422-6494	_____	_____	_____
Rieth – Riley Construction	5565 W. First Str. Ludington, MI. 49431 <u>Mailing:</u> P.O. Box 1173 Big Rapids, MI 49307 Email: rmisener@rieth-riley.com tlaman@rieth-riley.com	Ph: 231-845-7031 Fax: 231-845-5621	_____	_____	_____
Fischer Corp	3945 Bosschem Rd Wellston, MI. 49689	Ph: 231-510-5200 fax: 231-859-4320	_____	_____	_____
Elmer’s Concrete	3600 Rennie School Road P.O. Box 6150 Traverse City, MI. 49685 bpeace@teamelmers.com	Ph: 231-943-3443 fax: 231-943-5508	_____	_____	_____
Ken Adams Excavating	8770 North Oceana Drive P.O. Box 413 Pentwater, MI. 49449 Email: ken@michigandiggers.com	Ph: 231-869-5928 fax: 231-869-4620	_____	_____	_____
Peterson & Sons, LLC	1316 W. Marrison Rd Pentwater, MI. 49449 Cell: 231-425-8842 Email: petersons@hotmail.com	Ph: 231-869-5245 fax: 231-425-8842	_____	_____	_____
Schultz Excavating, LLC	5565 W. 6 th Street P.O. Box 683 Ludington, MI. 49431 Email: schultzexcavating@yahoo.com	Ph: 231-845-7172 fax: 231-843-4688	_____	_____	_____
Beckman Brothers Inc	3581 W Baker Road PO Box 268 Shelby MI 49455 Email: beckmanbros@frontier.com	Ph: 231-861-2031 fax: 231-861-5000	_____	_____	_____